



ADDENDUM 003

project	LCSD Hillcrest Elementary	project no.	18285
date	29 March 2019	contractor	DWA Construction
owner	Logan City School District	bid date	

This Addendum shall be considered part of the Contract Documents and Project Manual for the above mentioned project as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents and Project Manual, the Addendum shall govern and take precedence.

Drawings

Sheet	Description
AS101	<ul style="list-style-type: none">Deleted US mapDeleted Utah state mapRevised keynote 3209.0 to add "Contractor to install salvaged play toy as directed by owner"
AS401	<ul style="list-style-type: none">Revised keynote 3209.0 to add "Contractor to install salvaged play toy as directed by owner"Added detail callout for play toy ramp
AS402	<ul style="list-style-type: none">Deleted US mapDeleted Utah state mapRevised keynote 3209.0 to add "Contractor to install salvaged play toy as directed by owner"Added detail callout for play toy ramp
AS502	<ul style="list-style-type: none">Added play toy ramp detail
AS503	<ul style="list-style-type: none">Deleted US mapDeleted Utah state map
A111.3	<ul style="list-style-type: none">Removed LVT flooring pattern per accepted alternate
A112.4	<ul style="list-style-type: none">Updated awnings to standing seam per accepted alternate
A121.1	<ul style="list-style-type: none">Updated roof hatch type & location per accepted alternate
A121.2	<ul style="list-style-type: none">Relocated wall to coordinate w/ new roof hatch location
A121.4	<ul style="list-style-type: none">Updated roof hatch type & location per accepted alternate



ADDENDUM 003

- A122.1
 - Updated roof hatch type & location per accepted alternate
- A122.2
 - Added wall to coordinate w/ new roof hatch location
- A122.4
 - Updated roof hatch type & location per accepted alternate
- A130
 - Updated roof hatch type & locations per accepted alternate
- A131
 - Updated roof hatch type & location per accepted alternate
- A132
 - Updated roof hatch type & locations per accepted alternate
 - Updated awnings to standing seam per accepted alternate
- A201
 - Updated material tags & dimensions per accepted alternate
 - Updated awnings to standing seam per accepted alternate
 - Added additional dimensions for masonry control joint locations for clarification
- A202
 - Updated material tags & dimensions per accepted alternate
 - Updated awnings to standing seam per accepted alternate
 - Added additional dimensions for masonry control joint locations for clarification
- A203
 - Updated material tags & dimensions per accepted alternate
- A351
 - Updated detail A4 masonry coursing to 8" per accepted alternate
- A352
 - Updated details A1 & A6 masonry coursing to 8" per accepted alternate
- A354
 - Updated details A1, A3, & A4 masonry coursing to 8" per accepted alternate
- A400
 - Updated F4.1, F4.2, F4.3, F4.4, & F4.5 to VCT per accepted alternate
 - Updated EM1 to split-face
 - Updated EM4 to "Chili Pepper" w/ smooth face - 8"H x 16"L
 - Deleted Alt-EM4
 - Added EM5 - Amcor "Colonial Tan" w/ shot blasted face - 8"H x 16"L
 - Added MT6 - Standing seam metal roofing - MBCI; Signature 300 "Slate Gray"
- A407
 - Deleted plywood blocking from details C4 & A4
- A408
 - Updated countertops to plastic laminate per accepted alternate
- A409
 - Updated countertops to plastic laminate per accepted alternate
- A411
 - Deleted plywood blocking from detail E1
- A412
 - Deleted plywood blocking from details A5 & B4
- A451
 - Updated keynotes 502.6 & 502.7 to reflect the deletion of glazing per accepted alternate
 - Updated wall mounted handrails & detail reference to steel pipe per accepted alternate



ADDENDUM 003

- Updated keynote 502.9 to reflect change to steel per accepted alternate
- A453
 - Updated keynotes 502.6 & 502.7 to reflect the deletion of glazing per accepted alternate
 - Updated wall mounted handrails & detail reference to steel pipe per accepted alternate
 - Updated keynote 502.9 to reflect change to steel per accepted alternate
- A510
 - Updated details A4 & B2 to standing seam roof per accepted alternate
- A530
 - Deleted detail C4 per accepted alternate
- A540
 - Updated details D2, D3, & D4 to reflect steel guardrail per accepted alternate
- A550
 - Replaced details E4 & D4 w/ details from A551
 - Updated details E5 & C5 to refer plans for pipe type
 - Updated details D2 & D3 to reflect steel guardrail & handrail per accepted alternate
- A551
 - Deleted sheet
- A570
 - Deleted detail A5
- S131
 - Updated framing for roof hatch
- S132
 - Updated framing for roof hatches
- M401
 - Updated piping for relocated heat exchanger
- M402
 - Relocated heat exchanger due to new roof hatch location
- EP504
 - Deleted sheet

Specifications

Section	Description
07 5420	<ul style="list-style-type: none">• 1.9.A.3 - Delete "30 years" & replace with "20 years"• 2.1.A.1 - Delete "EXTRA 80 mil" & replace with "60 mil"• 2.1.A.2 - Delete "80 mil" & replace with "60 mil"• 2.1.A.3 - Delete "80 mil" & replace with "60 mil"• 2.1.C.1 - Delete in its entirety & replace with "Thickness: 60 mils, nominal, with minimum 24 mils above reinforcing"• 2.1.C.3 - Delete "350 lbf" & replace with "250 lbf"
08 7100	<ul style="list-style-type: none">• Updated hardware set #03 to include panic device per FM comments
32 3113	<ul style="list-style-type: none">• 2.1.D - Provide alternate finish per accepted alternate