

Park Valley School Park Valley School

Request for Proposal Information:

1. Remove and dispose of existing standing seam roof materials.
2. Contractor to provide protection board overlay prior to new roofing materials.
3. There will be (2) 5' x 5' double leaf roof hatches that need to be installed. Contractor has the option to furnish and install those roof hatches. Please note whichever option is chosen in your bids.
4. Contractor to furnish and install 60 mil TPO mechanically fastened roofing system.
5. All existing rooftop accessories/fixtures to remain. Contractor to furnish and install all necessary components and materials to provide and weather tight system.
6. All other requirements, conflicts, questions, or issues that may arise or need to be addressed will be discussed at the pre-bid meeting on March 11, 2024 @ 9:00AM. An final addendum will be issued prior to the bid date as outlined in the RFP documents.