



## DFCM SOLICITATION ADDENDUM COVER PAGE

### DFCM Addendum No.2

**Date:** April 25, 2024  
**To:** Interested Contractors  
**From:** Carl Francis-DFCM Project Manager  
**Reference:** Transchill Building Remodel  
Bridgerland Technical College  
DFCM Project 24139210

	<u>Pages</u>
Addendum Cover Page	1
Addition of Bid Alternate #1	1
<b>Total Pages:</b>	<b>2</b>

*Note:* This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to Disqualification.

- 2.1 Schedule Changes:** No schedule changes within this addendum.  
**2.2 General Items:** Add Bid Alternate #1: See Attached.

ADD BID ALTERNATE #1:

PROVIDE LINE-ITEM PRICING FOR THE FOLLOWING SCOPE OF WORK:

CLASSROOM 130

1. SAW CUT FLOOR IN OUTLINE SHOWN. FURNISH AND INSTALL FLOOR BOX WITH (1) 1" CONDUIT FOR POWER, (1) 1" CONDUIT FOR DATA, AND (1) 1-1/2" CONDUIT FOR AV. CONDUIT SHALL ROUTE FROM THE BACKBOX BEHIND THE TV TO THE FLOOR BOX. WHERE TWO OR THREE FLOOR BOXES ARE FURNISHED, PROVIDE POWER (1"), DATA (1"), AND AV (1-1/2") CONDUITS BETWEEN FLOOR BOXES. COORDINATE WITH GENERAL CONTRACTOR TO PATCH AND REPAIR DAMAGED FLOOR. REFER TO FLOOR BOX SCHEDULE FOR ADDITIONAL INFORMATION.

CLASSROOM 142

2. SAW CUT FLOOR IN OUTLINE SHOWN. FURNISH AND INSTALL FLOOR BOX WITH (1) 1" CONDUIT FOR POWER, (1) 1" CONDUIT FOR DATA, AND (1) 1-1/2" CONDUIT FOR AV. CONDUIT SHALL ROUTE FROM THE BACKBOX BEHIND THE TV TO THE FLOOR BOX. WHERE TWO OR THREE FLOOR BOXES ARE FURNISHED, PROVIDE POWER (1"), DATA (1"), AND AV (1-1/2") CONDUITS BETWEEN FLOOR BOXES. COORDINATE WITH GENERAL CONTRACTOR TO PATCH AND REPAIR DAMAGED FLOOR. REFER TO FLOOR BOX SCHEDULE FOR ADDITIONAL INFORMATION.