



## **Nielson Engineering, Inc.**

An Innovative Engineering Firm  
Consulting Engineers  
Electrical · Mechanical  
Information Systems · Petroleum

May 1, 2024

### **NORTH AND SOUTH CACHE MIDDLE SCHOOL BOILER REPLACEMENT ADDENDUM #1**

1. South Cache boiler room – Delete the existing condensate tank and pump. Disconnect the power, condensate, and make-up water piping.
2. South Cache boiler room – Locate the new feed water tank where the existing condensate tank was. Follow the plans key notes to connect the pressurized condensate, make-up water, drain, steam piping, and power.
3. North Cache boiler room – The boilers shall be supplied with control modules to sync the two boilers to alternate and work together if the steam load is large enough.