

ATTACHMENT 1

ACKNOWLEDGEMENT OF ADDENDA

Addendum Number	Addendum Date

UNIT PRICE BID SCHEDULE

Item No.	Description	Unit	Estimated Quantity	Bid Unit Price	Bid Price
1	Mobilization	LS	1		
2	Construction Surveying and Staking	LS	1		
3	Site Demolition and Preparation	LS	1		
4	Dewatering/Water Management	LS	1		
5	Furnish and Place Hot Mix Asphalt at Road Crossings	SY	690		
6	Site Restoration and Seeding	LS	1		
7	Traffic Control, Dust Control, and Maintaining Temporary Roadway	LS	1		
8	Furnish and Install Cast-in-Place Concrete Diversion Structure with One (1) 6' x 3' Gate Opening and One (1) 48" Diameter Pipe Opening	CY	75		
9	Furnish and Install 10' x 10' x 6" Cast-in-Place Concrete Pad at Diversion Structure for Screen Debris	CY	2		
10	Furnish and Install Grating on Diversion Structure	LS	1		
11	Furnish and Install One (1) 6' x 3' Waterman SS-250 Stainless Steel Slide Gate for Diversion Structure	EA	1		
12	Furnish and Install One (1) 48" Waterman C-10 Gate for Diversion Structure	EA	1		
13	Furnish and Install Debris Deflection on Diversion Structure	EA	1		
14	Furnish and Install Traveling Screen on Diversion Structure with Debris Trough	EA	1		

Item No.	Description	Unit	Estimated Quantity	Bid Unit Price	Bid Price
15	Electrical Work for 48" Waterman C-10 Canal Gate and Traveling Screen on Diversion Structure	LS	1		
16	Furnish and Install Temporary Riprap around Diversion Structure	CY	75		
17	Furnish and Install 48" Dual Wall Corrugated HDPE Pipe	LF	1200		
18	Furnish and Install 42" Dual Wall Corrugated HDPE Pipe	LF	2817		
19	Furnish and Install 30" Dual Wall Corrugated HDPE Pipe	LF	1664		
20	Furnish and Install 24" Dual Wall Corrugated HDPE Pipe	LF	57		
21	Furnish and Install 18" Dual Wall Corrugated HDPE Pipe	LF	77		
22	Furnish and Install 15" Dual Wall Corrugated HDPE Pipe	LF	44		
23	Furnish and Install 18" Reinforced Concrete Pipe	LF	152		
24	Furnish and Install 18" Corrugated Metal Pipe with Coupler Transition from Existing Pipe	LF	10		
25	Furnish and Install 35" x 23" Elliptical Corrugated Metal Pipe with Coupler Transition from Existing Pipe	LF	12		
26	Furnish and Install 6" EPDM Hose with Connection Fittings (2) for 6" Steel Well to EPDM Hose	LF	28		
27	Furnish and Install 4' x 4' x 6' Precast Concrete Inlet Box with 4 Openings	EA	1		
28	Furnish and Install 6' x 6' x 8' Precast Concrete Inlet Box with 3 Openings	EA	3		
29	Furnish and Install 8' x 8' x 8' Precast Concrete Inlet Box with 3 Openings	EA	1		
30	Furnish and Install 4' x 4' x 5' Precast Concrete Cleanout Box with 2 Openings	EA	1		
31	Furnish and Install 4' x 4' x 8' Precast Concrete Cleanout Box with 3 Openings	EA	1		
32	Furnish and Install 6' x 6' x 8' Precast Concrete Cleanout Box with 3 Openings	EA	2		
33	Furnish and Install 6' x 6' x 8' Precast Concrete Cleanout Box with 2 Openings	EA	1		
34	Furnish and Install 4' x 4' x 6' Precast Concrete Diversion Box with 3 Openings, One (1) 18" Waterman C-10 Gate, and One (1) 15" Waterman C-10 Gate	EA	1		
35	Furnish and Install 6' x 6' x 8' Precast Concrete Diversion Box with 3 Openings and One (1) 30" Waterman C-10 Gate	EA	2		

Item No.	Description	Unit	Estimated Quantity	Bid Unit Price	Bid Price
36	Furnish and Install 6' x 6' x 8' Precast Concrete Diversion Box with 4 Openings and Two (2) 18" Waterman C-10 Gates	EA	2		
37	Furnish and Install 6' x 8' x 8' Cast-in-Place Concrete Check Box with 4 Openings, One (1) 18" Waterman C-10 Gate, One (1) 24" Waterman C-10 Gate, and One (1) 4' x 5' Waterman SS-250 Stainless Steel Slide Gate	EA	1		
38	Furnish and Install 6' x 8' x 8' Cast-in-Place Concrete Check Box with 4 Openings, Two (2) 18" Waterman C-10 Gates, and One (1) 4' x 3' Waterman SS-250 Stainless Steel Slide Gate	EA	1		
39	Furnish and Install 6' x 8' x 8' Cast-in-Place Concrete Check Box with 3 Openings, One (1) 18" Waterman C-10 Gate, and One (1) 4' x 5' Waterman SS-250 Stainless Steel Slide Gate	EA	1		
40	Furnish and Install 8' x 9' x 9' Cast-in-Place Concrete Overflow Box with 3 Openings, One (1) Weir Wall, and One (1) 30" Waterman C-10 Gate	EA	1		
41	Furnish and Install 4' Diameter x 6' Concrete Manhole with 2 Openings	EA	4		
42	Furnish and Install 4' Diameter x 6' Concrete Manhole with 1 Opening	EA	1		
43	Furnish and Install 4' Diameter x 8' Concrete Manhole with 1 Opening	EA	1		
44	Furnish and Install 6' Diameter x 8' Concrete Manhole with 2 Openings	EA	1		
45	Furnish and Install 7' Diameter x 8' Concrete Manhole with 3 Openings	EA	1		
46	Furnish and Install 42" Concrete Flared End Outlet	EA	1		
47	Furnish and Install 30" Concrete Flared End Outlet	EA	3		
48	Furnish and Install 18" Concrete Flared End Outlet	EA	1		
49	Furnish and Install 18" Concrete Flared End Inlet with Trash Rack	EA	3		
					\$