

BID SCHEDULE

Item	Description	Unit	Quantity	Unit Price	Item Price
1	Mobilization	Lump Sum	1		
2	Traffic Control	Lump Sum	1		
3	Survey	Lump Sum	1		
4	Storm Water Pollution Prevention Plan (SWPPP)	Lump Sum	1		
5	Sawcut Existing Asphalt/Concrete	Lineal Foot	547		
6	Remove Existing Concrete and Asphalt	Square Foot	1,297		
7	Remove Existing Fence Line	Lineal Foot	309		
8	Excavation/Site Fill and Preparation	Lump Sum	1		
9	3x3 Stormwater Junction Box	Each	1		
10	4x4 Stormwater Junction Box	Each	1		
11	Construct 15-inch Concrete Piping	Lineal Foot	43		
12	Construct 36-inch Concrete Piping	Lineal Foot	79		
13	Construct Keystone Retaining Wall	Lineal Foot	190		
14	Construct Curb Wall & Guardrail	Lineal Foot	190		
15	Reinstall Fence	Lineal Foot	309		
16	Compacted Base Course	Square Foot	13,500		
17	Compacted Granular Borrow	Cubic Yard	1,275		
18	Construct New Concrete Sidewalk	Square Foot	4,387		
19	Construct Concrete Pavement at Approach	Square Foot	130		
20	Construct Asphalt Pavement	Square Foot	8,654		
21	Construct Curb and Gutter	Lineal Foot	532		
22	Construct Park Strip Drainage Swale	Lineal Foot	532		
23	Construct Irrigation Drainage Ditch	Lineal Foot	194		
24	Install Fire Hydrant Assembly	Each	1		
25	Landscaping and Irrigation	Lump Sum	1		
26	Quality Control and Testing	Lump Sum	1		
27	BID ALT – Install 2” Street Lighting Conduit per Rocky Mountain Power Requirements	Lineal Foot	150		