

BID SCHEDULE

CONTRACT FOR: Birch Creek Water Project

The undersigned Bidder, having examined and determined the scope of the Contract Documents, hereby proposes to perform the work described herein for the following unit prices or lump sum amounts.

Note: *Bids shall include sales tax and all other applicable taxes and fees.
All bids shall be checked for errors. If errors are made, unit prices shall govern and corrections will be made according to the unit price*

No.	Meas. & Pmt.	Item	Quantity	Unit	Unit Price	Amount
General Project Items						
1	02000	Mobilization	1	L.S.		
2	02005	Traffic Control	1	L.S.		
3	02020	Subsurface Investigation - Main Line	6	HR		
4	02020	Subsurface Investigation - Service Lines	18	HR		
5	SP 02200	Dewatering	10	DAYS		
6	02510	Material Sampling and Testing	1	L.S.		
Demolition and Surface Restoration						
7	02520	Sawcutting Asphalt	1,000	LN.FT.		
8	02500	Remove Bituminous Surface	444	SQ.YD.		
9	02500	Replace 3" HMA PG 58-34 Bituminous Surface	444	SQ.YD.		
10	02500	Remove & Replace Chain Link Fence	20	LN.FT.		
11	02500	Remove & Replace Stock Fence and Gates	153	LN.FT.		
12	SP 02900	Field Seed Mix Material for Trenching	0.6	Acre		
13	SP 02900	Restore Landscaping Parcel RP03956.01	1	L.S.		
Main Line Replacement and Appurtenances						
14	02222	Install 4" DR25 C-900 PVC Pipe	5,850	LN.FT.		
15	02222	Install 24" DR25 C-900 PVC Pipe	160	LN.FT.		
16	02320	Piped Encasement (10" Corrugated HDPE)	30	LN.FT.		
17	SP 15110	Connect 24" Pipe to 4" Pipe	2	EA		
18	SP 15110	Install New Spring Box Intake Pipe	1	L.S.		
19	02250	Install Clay Cutoff Wall at Water Crossings	6	EA		
20	SP 15110	Install Riprap at Creek Crossing	2	EA		
21	15232	Install 1" Combination Air/Vacuum Valve (24" Tap)	1	EA		
22	15232	Install 1" Combination Air/Vacuum Valve (Tank)	2	EA		
23	SP 15110	Install Main Line Drain Pipe & End Protection	1	L.S.		

24	SP 15110	Install Tank Drain Pipe End Protection	1	L.S.		
25	SP 15110	Install Tank Overflow Air Gap Assembly	1	L.S.		
26	15230	Install 4" Gate Valve - Inside Tank	4	EA		
27	15230	Install 4" Gate Valve - Outside Tank	4	EA		
28	SP 15110	Connect to Existing Pipe	7	EA		
29	01019	Install Spill Containment Pallet	1	L.S.		
Service Connections						
30	SP 15234	Install 1" Service Connection	10	EA		
31	15234	Install 1" Service Meter Assembly	40	EA		
32	15234	Install Water Meters	40	EA		
Spring Protection						
33	SP 02015	Clear and Grub Spring Surroundings	1	L.S.		
34	SP 02210	Install Cutoff Ditch	200	LN.FT.		
35	02900	Re-seeding Spring Surround	0.1	Acre		
36	SP 02210	Install Erosion Control Mat Spring Surround	2,750	SQ.FT.		
BASE BID TOTAL						

Bid Alternate 1: Additional Spring Protection						
37	SP 02210	Strip and Replace 6" Topsoil for Spring Liner	300	SQ.YD.		
38	SP 02210	Install 40 Mil HDPE Spring Liner	2,750	SQ.FT.		
39	SP 02210	Install 1' Thick Spring Clay Liner	300	SQ. YD.		
40	SP 02900	Re-Seeding Labor for Trenching	0.6	Acre		
BID ALTERNATE 1 TOTAL						

The undersigned Bidder certifies that this proposal is made in good faith, without collusion or connection with any other person or persons bidding on the work.

Seal (if bid is by Corporation)

Respectfully Submitted:

Bidder: _____

Signature _____

Title: _____

License No. _____

Address: _____

Date: _____
