

BIRCH CREEK WATER PROJECT

ADDENDUM #3

May 15, 2026

PLANHOLDER:

This Addendum #3 shall become part of the plans, specifications, and contract documents of the above referenced project, and all provisions of the contract shall apply hereto.

Bidders shall acknowledge receipt of all addenda by number in the space provided in the bid documents.

This Addendum #3 covers the following items:

- Addressing questions that have been received throughout the bidding process (as of 5/15/26 @ 12:00 pm)

The ENGINEER stopped receiving questions as of May 15th at 12:00 PM. Any additional questions received after this time will not be answered.

Questions and Answers

Below are the questions that have been submitted with their corresponding answers:

Q: Sourcing pit run clay that meets the specification of 100% passing the #200 sieve may be difficult, is this a strict standard?

A: 02210.2.3 specifies that "Clay – Material shall be "pit run bentonite" and shall exhibit a permeability of 1×10^{-6} cm/sec. In addition, the material shall pass the No. 200 sieve and have a plasticity index greater than 12. Material shall be free of cinders, ashes, wood, and vegetation; frozen or other deleterious materials." This specification is required for this project for drinking water source protection at the spring.

Sincerely,

Seth Thompson, PE
Sunrise Engineering

