

Issued: 9/15/2026

BID SCHEDULE - PRIMARY PIPE BID

CONTRACT FOR: WCIC BUTTARS LATERAL CANAL PIPING PROJECT

The undersigned Bidder, having examined and determined the scope of the Contract Documents, hereby proposes to perform the work described herein for the following unit prices or lump sum amounts.

Note: Bids shall include sales tax and all other applicable taxes and fees.

All bids shall be checked for errors. If errors are made, unit prices shall govern and corrections will be made according to the unit price

No.	Meas. & Pmt.	Item	Quantity	Unit	Unit Price	Amount
General Items						
1	2000	Mobilization	1	L.S.		
2	2005	Traffic Control	1	L.S.		
3	2510	Materials Sampling and Testing	1	L.S.		
4	1560	Construction Staking	1	L.S.		
5	2020	Subsurface Investigation	10	HR		
Sub-Total						-
Pressurized Pipeline						
6	2222	Install C900 DR-32.5 30" Pipe and Fittings	3,940	L.F.		
7	2222	Install C900 DR-32.5 24" Pipe and Fittings	1,940	L.F.		
8	2222	Install C900 DR-32.5 15" Pipe and Fittings	1,600	L.F.		
9	2222	Install C900 DR-32.5 12" Pipe and Fittings	460	L.F.		
10	2222	Install C900 DR-32.5 10" Pipe and Fittings	6,240	L.F.		
11	2222	Install C900 DR-32.5 8" Pipe and Fittings	6,800	L.F.		
12	2222	Install C900 DR-32.5 4" Pipe and Fittings	2,300	L.F.		
13	2105	Imported Pipe Bedding	23,280	L.F.		
14	15230	24" Butterfly Valve	1	EA		
15	15230	15" Butterfly Valve	1	EA		
16	15230	10" Butterfly Valve	2	EA		
17	15230	8" Butterfly Valve	1	EA		
18	15232	3" Combination Air/Vacuum Relief Valve Assembly	8	EA		
19	SP15231	8" Pipeline Drain	1	EA		
20	SP15231	4" Pipeline Drain	4	EA		
21	SP13300	Install 15" Service Connection Assembly	1	EA		

22	SP13300	Install 10" Service Connection Assembly	2	EA		
23	SP13300	Install 8" Service Connection Assembly	2	EA		
24	SP13300	Install 6" Service Connection Assembly	6	EA		
25	SP13300	Install 4" Service Connection Assembly	11	EA		
26	SP13300	Install 2" Service Connection Assembly	1	EA		
27	SP13500	UDOT Road Crossing #1 (12890 N 4800 W Open Cut)	1	L.S.		
28	SP13600	UPRR Railroad Crossing #2 (Boring and Jacking)	1	L.S.		
29	SP13500	Cornish Road Crossing #3 (12240 N 4800 W Open Cut)	1	L.S.		
30	SP13500	Cornish Road Crossing #4 (12300 N 4400 W Open Cut)	1	L.S.		
31	2222	Pipeline Location Markers	26	EA		
32	SP2003	Removal of Existing Concrete Structures	7	EA		
33	SP2003	Removal of Existing Concrete Ditch Segments	275	L.F.		
34	SP2003	Reclamation of Existing Ditches	10,200	L.F.		
35	2900	Re-seeding and Restore Landscaping	0	L.F.		
36	SP2003	Restoration of Gravel Road	240	L.F.		
37	SP2003	Maintenance of Gravel Road	1	L.S.		
Sub-Total					-	
Intake Structure & Pump Station Estimated Price Ranges						
Description			Low		High	
38	SP13200	Intake Diversion Structure				
39	SP13200	Pump Station				
Sub-Total			-		-	
TOTAL (not including Intake and Pump considerations)						\$ -

The undersigned Bidder certifies that this proposal is made in good faith, without collusion or connection with any other person or persons bidding on the work.

Seal (if bid is by Corporation)

Respectfully Submitted:

Bidder: _____

Signature: _____

Title: _____

License No. _____ Address: _____

Date: _____