

BID SCHEDULE

NOTE: Bidder agrees to perform all the work described in the CONTRACT DOCUMENTS for the following unit prices. Bid prices shall include all applicable taxes and fees.

Cub River Wetland Mitigation Site

August 2026

North Logan Wetland Mitigation Area Bid						
Item No.	APWA Spec.	Classification of Work	QTY	Unit	Unit Price	TOTAL Cost
1	01 57 00	Temporary Controls Create and Implement Storm Water Pollution Prevention Plan (SWPPP)	1	Lump Sum		
2	01 71 13	Mobilization and Demobilization (10%)	1	Lump Sum		
3	01 71 23	Construction Layout	1	Lump Sum		
4	01 57 00	Stabilized Construction Entrance.	1,000	Square Feet		
5	01 57 00	Silt Fence	1,500	Linear Feet		
6	06 61 00	Rail Fence	1,020	Linear Feet		
7	31 05 13	Common Fill. Includes borrow from on-site excavation	5,100	Cubic Yard		
8	31 11 00	Site Clearing. Clear and Grub.	17,000	Square Yard		
9	31 23 16	Strip, Stockpile and Spread Topsoil	17,000	Square Yard		
10	31 23 16	Strip, Stockpile and Spread Topsoil in farm field Landscape Grading areas.	18,360	Square Yard		
11	31 23 16	Excavation. Cut (Cut 8900 CY minus Fill 5100 = CY)	3,800	Cubic Yard		
12	32 91 19	Landscape Grading. Includes placing backfill material on farm field.	3,800	Cubic Yard		
13	32 92 00	Turf and Grass. Supply and install WETLAND FRINGE SEED MIX and hydro mulch.	0.2	Acre		
14	32 92 00	Turf and Grass. Supply and install EMERGENT WETLAND SEED MIX and hydro mulch.	1.3	Acre		
15	32 92 00	Turf and Grass. Supply and install UPLAND SEED MIX and hydro mulch.	1.0	Acre		
16	32 93 13	Ground Cover. Supply and install shrubs (40 cu in).	1,700	Each		
17	32 93 43	Tree. Supply and Install trees (5 gal).	230	Each		
18	32 93 43	Supply and Install Wire Cage at Populus tree species	80	Each		
19	32 01 90	Maintenance of Planting. Includes water, weed, repair and protect installed plantings until work is accepted.	1	Lump Sum		
20	33 05 06	Culvert with Flap Gate	3	Each		
21	33 05 06	Culvert with Control Gate	1	Each		
North Logan Wetland Mitigation Area Total Bid (\$): _____						

Hyde Park Wetland Mitigation Area Bid						
Item No.	Classification of Work		QTY	Unit	Unit Price	TOTAL Cost
1	01 57 00	Temporary Controls Create and Implement Storm Water Pollution Prevention Plan (SWPPP)	1	Lump Sum		
2	01 71 13	Mobilization and Demobilization (10%)	1	Lump Sum		
3	01 71 23	Construction Layout	1	Lump Sum		
4	01 57 00	Stabilized Construction Entrance.	1,000	Square Feet		
5	01 57 00	Silt Fence	800	Linear Feet		
6	06 61 00	Rail Fence	920	Linear Feet		
7	31 05 13	Common Fill. Includes borrow from on-site excavation	4,900	Cubic Yard		
8	31 11 00	Site Clearing. Clear and Grub.	16,000	Square Yard		
9	31 23 16	Strip, Stockpile and Spread Topsoil	16,000	Square Yard		
10	31 23 16	Strip, Stockpile and Spread Topsoil in farm field Landscape Grading areas.	27,540	Square Yard		
11	31 23 16	Excavation. Cut (Cut 11100 CY minus Fill 4900 = CY)	6,200	Cubic Yard		
12	32 91 19	Landscape Grading. Includes placing backfill material on farm field.	6,200	Cubic Yard		
13	32 92 00	Turf and Grass. Supply and install WETLAND FRINGE SEED MIX and hydro mulch.	0.1	Acre		
14	32 92 00	Turf and Grass. Supply and install EMERGENT WETLAND SEED MIX and hydro mulch.	1.4	Acre		
15	32 92 00	Turf and Grass. Supply and install UPLAND SEED MIX and hydro mulch.	1.1	Acre		
16	32 93 13	Ground Cover. Supply and install shrubs (40 cu in).	850	Each		
17	32 93 43	Tree. Supply and Install trees (5 gal).	250	Each		
18	32 93 43	Supply and Install Wire Cage at Populus tree species	100	Each		
19	32 01 90	Maintenance of Planting. Includes water, weed, repair and protect installed plantings until work is accepted.	1	Lump Sum		
20	33 05 06	Culvert with Flap Gate	2	Each		
Hyde Park Wetland Mitigation Area Total Bid (\$): _____						

Signature of Preparer: _____