NIBLEY CITY REGIONAL DRAIN LINE
Bidding Q & A

Questions/Answers November 4, 2026

Question # 1. Bid Item 9 (24-inch Slide Gate): It looks like the quantity may have been left off the Bid Schedule. Could you let us know how many are intended? The Measurement and Payment description for Item 9 also seems to repeat the 12-inch gate language from Item 8, so we wanted to confirm the size.

City Response #1-
The unit and quantity for Bid Item #9 were not included in the original bidding documents. Addendum #1 will address this.

Question #2. Slide gate locations: The plans appear to show slide gates at Boxes 3, 4, 6, 7, 8, and 9, and the Box 9 detail seems to show gates on both the 24-inch and 12-inch outlets. Item 8 lists five 12-inch gates, so we want to be sure we're counting these the way you intend. Could you confirm the size and location of each one?

City Response #2-
12-inch slide gates are called out on Box numbers 4, 6, 7, 8 and 9.
24-inch slide gate is called out on Box 9.

Question #3. Detail 2/C501 (Stormwater Structure): The general notes refer to this detail for the boxes, but it appears blank on our copy of sheet C501. Is there a detail we should be using, or should we build the boxes to APWA as amended by Nibley City Plan No. 332?

City Response #3-
General Notes #4 on sheet C200 is incorrect. Addendum #1 will address this.

Question #4. 15-inch Piping (Item 13): We weren't able to find lengths or a profile for the 15-inch line. Could you confirm the limits of that work and whether the existing 15-inch between the existing storm drain boxes is being replaced?

City Response #4-
15-inch pipe location and lengths are shown on sheet C402 and a short section on Sheet C401. There are no profiles for these sections of 15-inch pipe.

Question #5. Qualification Form: The instructions mention experience on projects funded by similar federal programs. Would you be able to share which program is funding this project? It would also help to know whether any federal requirements apply, like Davis-Bacon wages or

Buy America provisions.

City Response #5-
The mention of federal funding is an error. Experience on federal projects is not required.

Question #6. Bid hold period: We noticed the Instructions mention 90 days and the Proposal mentions 30 days. Which should we plan on?

City Response #6
The City has the right to reject bids if action is taken within 30 days. Bid Bond Hold is 90 days.

Question #7. Construction window: Since the irrigation season generally starts April 1, is the City hoping to have the canal and pipe work wrapped up before then? Or has there been some discussion with College Irrigation Company about working into the season?

City Response #7-
Final completion is June 30 and punch list items by July 1. Work during irrigation season will need to be coordinated with the canal company(ies). The city has coordinated the extent of the work with the canal company. Contact information for the College Irrigation Company is included in GENERAL AND SPECIAL PROVISIONS for coordination of watering schedules and work that impacts the canal.

Question #8. Pre-bid meeting / site visit: We didn't see a pre-bid meeting in the documents. Is one planned? If not, would it be OK for us to walk the alignment, and is there anything we should do before going onto the private properties?

City Response #8-
There is no mandatory pre-bid nor site visit. The site can be accessed from Maple Valley Rd (1500 West) via 3200 South. There is a drainage easement shown on the plans. Visitors should remain within the easement during any site visit.

Question #9. Engineer's estimate: If the City is able to share the engineer's estimate or project budget, it would be helpful to us.

City Response #9-
The project is estimated near $230,000.

Question #10. Soils and groundwater: Is there any geotechnical or groundwater information available for the alignment? Also, should we plan on the existing 10-inch land drain staying in service during construction?

City Response #10-
There is no geotechnical information available.
Soil Types are estimated to be loam, silty clays, silty clay loams, and clay loams.
Groundwater is estimated to be between 24 and 48 inches below existing grade.

NIBLEY CITY REGIONAL DRAIN LINE
Bidding Q & A

Question #11. Also, should we plan on the existing 10-inch land drain staying in service during construction?

City Response #11-
The existing land drain must remain in service during construction.